# Steel Shell For Pour In Place Installation 6 Ft. x 6 Ft. Brown

**MODEL SS/66**

Loading Dock Equipment / Electric Hydraulic Dock Levelers

*Product image unavailable*

## PRODUCT OVERVIEW

Optional steel shell for 72 (in.) by 72(in.) Pour in place installation. The steel shells are installed when the concrete is being poured, to provide steel panels on each vertical face of the pit, along with steel flanges along the top faces. Proper installation of a dock leveler requires the leveler to be welded along the upper rear edge of the pit, and the steel shells provide this edge. The steel shells include a front lower steel angle, that gets placed at the front bottom of the pit. This angle provides another essential location where the leveler needs to be welded to the pit.

## KEY FEATURES

- Optional steel shell for ideal operation
- Ideal for 72" x 72" pour in place installation for maximum efficiency
- Features durable construction for added strength and long life
- Use in industrial applications for optimal results

## CORE PRODUCT DATA

| | | |
|---|---|---|
| ASSEMBLED WEIGHT<br>**301 lbs** | ASSEMBLED SIZE<br>**80" W x 65" L x 24" H** | SHIP WEIGHT<br>**301 lbs** |
| PACKAGE 1 SIZE<br>**80" W x 65" D x 24" H** | COLOR / FINISH<br>**Brown** | FREIGHT TYPE<br>**LTL Palletized** |

**AVAILABILITY** Available **QUICKSHIP: --**

Products are sold through Vestil distributor partners. Contact a distributor for current pricing and ordering.

**ADDITIONAL PRODUCT VIEWS**



## PRODUCT SPECIFICATIONS

| | |
|---|---|
| **Maximum Board Width (In)** | 80 |
| **Attachment Method** | Concrete pour in place |
| **Package Contents** | (1) Steel Shell for Dock Levelers |

## PRODUCT & SHIPPING REFERENCE

Shipping Point: **Angola, IN 46703**

Warranty: **90 Days**

**AVAILABLE PRODUCT RESOURCES**

**SCAN FOR CURRENT PRODUCT DATA**

Live product page: https://www.vestil.com/product.php?EID=4